LINEN CABINET



ELEVATION (DOORS CLOSED)
SCALE: 1/2" = 1'-0"



PLAN
SCALE: 3" = 1'-0"



ELEVATION (DOORS REMOVED)
SCALE: 1/2" = 1'-0"

SECTION
SCALE: 1/2" = 1'-0"



DETAIL
ADJUSTABLE
DOWEL RACK
SCALE: 3" = 1'-0"



ELEV. NORTH WALL
SCALE: 1/2" = 1'-0"



ELEV. EAST WALL
SCALE: 1/2" = 1'-0"



SECT. THRU HAMPER
SCALE: 1/2" = 1'-0"



HALF PLAN OF HAMPER
SCALE: 1/2" = 1'-0"

LAUNDRY

ROOM FINISH SCHEDULE

ROOM	FLOOR	WALLS	CEILING	BASE	TRIM	CORNICE	NOTES
HALL #1	TERRAZZO	PLASTER & BRICK	ACOUSTICAL PLASTER	METAL	METAL CASING BEAD	NONE	
HALL #2	"	PLASTER	"	"	"	"	
LIVING #1	"	PLASTER & BRICK	"	"	"	"	
LIVING #2	"	PLASTER	"	"	"	"	
DINING	"	PLASTER & BRICK	"	"	"	"	
KITCHEN	"	PLYWOOD	"	NONE	WOOD	"	
BEDROOM #1	"	PLASTER & BRICK	"	METAL	METAL CASING BEAD	"	
BEDROOM #2	"	"	"	"	"	"	
BEDROOM #3	"	PLASTER	"	"	"	"	
BEDROOM #4	"	"	"	"	"	"	
STORAGE #1	"	PLASTER & BRICK	PLASTER	"	"	"	
BATH #1	"	PLASTER	ACOUSTICAL PLASTER	"	"	"	MARBLE TILE 2 SIDES TUB
BATH #2	"	"	"	"	"	"	"
LAUNDRY	"	"	"	"	"	"	
HEATING & A.C.	CONCRETE	"	PLASTER	"	NONE	"	
STORAGE #2	"	BRICK,	UNFINISHED	NONE	"	"	
GARAGE	"	"	PLYWOOD	"	"	"	
GALLERY	TERRAZZO	"	"	"	"	"	

DOOR SCHEDULE

DOOR	SIZE	TYPE	FACE VENEER
A	3'-0" x 6'-8" x 1 3/4"	SOLID CORE FLUSH	SLICED WALNUT
B	3'-0" x 6'-8" x 1 3/4"	" " "	GUM - PAINT GRADE
C	2'-8" x 6'-8" x 1 3/4"	" " "	" " "
D	2'-0" x 6'-8" x 1 3/4"	" " "	" " "
E	6'-0" x 8'-0" x 1 3/8" (TWO 3'-0" x 8'-0" DOORS JOINED)	HOLLOW CORE FLUSH	" " "
F	3'-0" x 8'-0" x 1 3/8"	" " "	" " "
G	2'-8" x 6'-8" x 1 3/8"	" " "	" " "
H	2'-4" x 6'-8" x 1 3/8"	" " "	" " "
J	2'-0" x 6'-8" x 1 3/8"	" " "	" " "

RESIDENCE for
DR. & MRS. L. EVERETT SAWYER
ELIZABETH CITY, N. C.

SHEET 10 OF 10

ED PUGH JR., A.I.A.
ARCHITECT
ELIZABETH CITY, N.C.

April 1958