
ROOF AS SPECIFIED
3/4" T & G ROOFERS
SAME AS SECT AT "A"
2"x4"
2"x6" J. 16" o.c.
2"x6
3/8" BOLTS. 2'-0" o.c. STAGGERED. WELD TO L.
BRONZE SCREENING
1/2" PLYWOOD
4"
4"
6"x4"x3/8" L
3 1/2" STD. PIPE COL.
SCALE: 3" = 1'-0"
2"x10" J. 16" o.c.
TWO - 2"x4"s.
1/2" PLYWOOD
2"x4" STUDS 16" o.c.
1/2" PLYWOOD
2"x4"
2"x12"
3/8" BOLTS. 2'-0" o.c. STAGGERED
10" I 25.4
7'-6" TO SLAB
SCALE: 3" = 1'-0"
2"x6" J. 16" o.c.
1/2" PLYWOOD
3/8" BOLTS. 2'-0" o.c. STAGGERED
12" I 31.8
SCALE: 3" = 1'-0"
SAME AS SECT AT "A"
2"x4"
BRONZE SCREENING
2"x6"
4"
3/8" ANCHOR BOLT AT EACH PIER
SCALE: 3" = 1'-0"
SAME AS AT SECT "A"
2"x4" x 8'-0" LONG SPIKE TO EACH 2"x10"
BRONZE SCREENING
3/4" PLYWOOD
2"x10" 16" o.c.
3'-6"
SECT. AT E
SCALE: 3" = 1'-0"
4" CONC. SLAB. MESH REINF.
SAND FILL
REMOVE TOPSOIL TO TOPS FORMS & USE FOR GRADING
TWO 1/2" ϕ RODS
SECT. AT B
SCALE: 1/4" = 1'-0"
2"x4"
SAME AS SECT AT "A"
2"x4" 16" o.c.
2"x10" J 16" o.c.
WALL TIES AS SPECIFIED EVERY 6TH COURSE
ACOUSTICAL PLASTER
3/8" BOLT. 6'-0" o.c.
1/4"x1"x8" STEEL BAR
SPOT WELD
3 3/4"
2"
3 3/4"
TYPICAL CAVITY BRICK WALL
SCALE: 3" = 1'-0"
SCALE: 3" = 1'-0"
TERRAZZO
FIN. FL. LEVEL
16 OZ. COPPER. LOCKED & SOLDERED SEAMS
WEEP HOLES 16" o.c.
1'-4 1/2"
SCALE: 3" = 1'-0"
1/2" ϕ ROD
1'-6"
FIN. FL. HOUSE
3 1/2" STD. PIPE COL.
3"x8"x1/4" PL.
1/2" GROUT
4-1 1/2"x8" BOLTS
DRIVE LEVEL
MESH REINF.
CONCRETE
5"
CONC. PEDESTAL
GARAGE FL. LEVEL
CONCRETE
MESH REINF.
1/2" EXP. JOINT
SAND FILL
APPROX. NAT GRADE
CONC. FOOTING
2"x10" 16" o.c.
2"x6" 16" o.c.
2"x4" 16" o.c.
RETURN AIR PLENUM
SECT. AT D
SCALE: 1/4" = 1'-0"
SAME AS SECT "A"
5'-0"
LATH & PLASTER
2"x4" STUDS 16" o.c.
3" METAL BASE
TWO 2"x4"s
TERRAZZO
TERRAZZO
CONCRETE
SECT. AT C
SCALE: 1/4" = 1'-0"
SCALE: 3" = 1'-0"
RESIDENCE FOR
DR. & MRS. L. EVERETT SAWYER
ELIZABETH CITY, N. C.
SHEET
ED PUGH JR. A.I.A.
ARCHITECT
ELIZABETH CITY, N.C.
April 9, 48